

Complete Mold Dump/Shakeout/ Runaround System

Castings & Sand

Cast Metal: Brass
Sand: 28 TPH
Castings: 3 TPH
Mold Process: Green Sand
Mold Size: 14" x 19" x 8"/8"

- System designed to process sand and castings continuously. Engineered to fit into a small space and efficiently shakeout and sort.
- Mold Dump Conveyor approximately 20'-0" lg.
- Delta Phase Shakeout approximately 11'-0" lg.
- Castings and Return Sand Conveyor Double Pan approximately 40'-0" lg (with S/S liner).
- Castings Return Conveyor approximately 25'-0" lg. Total Capacity 31 TPH @ 80 PCF.

